





CHISLEY™ PANEL ©2017 modularArts, Inc.
32" X 32"
1/4" MINIMUM TO 1" MAXIMUM
CAN BE INSTALLED VERTICALLY OR HORIZONTALLY. "THIS SIDE UP" IS DEFINED ON
PANELS AS THE INTENDED ORIENTATION FOR LIGHT AND SHADOW.
1.4 LBS/SQ FT
32"
GRG (GLASS REINFORCED GYPSUM) 100% NON-COMBUSTIBLE MINERAL
PRECAST MOUNT-POINTS. SELF-ALIGNING EDGES WITH STEEL REINFORCED JOINTS.
NEW OR EXISTING WALLS. TYPICALLY INSTALLED DIRECTLY TO DRYWALL. MAY BE APPLIED TO A VARIETY OF SUBSTRATES (PLEASE REFER TO INSTRUCTION BOOKLET). DO NOT APPLY DIRECTLY TO STUDS.

## INSTALLATION SUMMARY

- $\cdot$  PANELS ARE SCREW-MOUNTED THROUGH THE FACE TO THE SUBSTRATE (TYPICALLY DIRECT TO DRYWALL).
- · ALL PANEL-TO-PANEL EDGES ARE GLUED WITH APPROVED ADHESIVE AS PANELS ARE MOUNTED.
- $\cdot\,$  SEAMS ARE FILLED WITH THE APPROVED SPACKLING COMPOUND.
- · SEAMS ARE SANDED.
- · SURFACE IS SEALED WITH THE APPROVED PRIMER/SEALER.
- · DESIRED FINISH PAINT IS APPLIED (FLAT PAINT RECOMMENDED, SPRAY APPLICATION PREFERABLE).

## ADDITIONAL NOTES

- ONE MAN-HOUR PER PANEL SHOULD BE ALLOTTED TO MOUNT AND SEAM PANELS PRIOR TO PAINT. (DRYING TIME NOT INCLUDED). EXPERIENCE MAY SHORTEN INSTALLATION TIME.
- · A DETAILED INSTALLATION BOOKLET ACCOMPANIES EACH ORDER.

2/06/23

## modulararts<sup>®</sup>