## DAKOTA™







DAKOTA™ EZ-Seam™

VOTATM PANIEL COOKS
KOTA™ PANEL ©2018 modularArts, Inc.
PANEL COVERS 5.92 SQ FT, 32" H X 32" W AT MAXIMUM
IDE PANEL COVERS 4.75 SQ FT, 32" H X 21.5" W STAGGERED
MINIMUM TO 1" MAXIMUM
OOSE STARTING EDGE FOR END PANEL, AND ROTATE ACCORDINGLY.
TATE EVERY OTHER INSIDE PANEL TO AVOID REPEATING PLANKS.
3S/SQ FT
ROTATED
G (GLASS REINFORCED GYPSUM) 100% NON-COMBUSTIBLE MINERAL
N OR EXISTING WALLS. TYPICALLY INSTALLED DIRECTLY TO DRYWALL.
Y BE APPLIED TO A VARIETY OF SUBSTRATES (PLEASE REFER TO TRUCTION BOOKLET). DO NOT APPLY DIRECTLY TO STUDS.

## **INSTALLATION SUMMARY**

- · PANELS ARE SCREW-MOUNTED THROUGH THE FACE TO THE SUBSTRATE (TYPICALLY DIRECT TO DRYWALL).
- · SEAMS ARE CAULKED WITH A MINIMAL BEAD. (50 YEAR, WHITE, PAINTABLE RECOMMENDED)
- $\cdot \ \, \text{MOUNT-POINTS ARE FILLED AND SANDED WITH THE APPROVED FILLER (OR SIMPLY CAULKED):} \\ \underline{ \ \, \text{DAP All-Purpose Spackling Paste}}$

(AVAILABLE AT HOME DEPOT). FILLER MATCHES THE PANEL COLOR.

• OPTIONAL (FOR PAINT OR EXTRA PROTECTION): SURFACE IS SEALED WITH CLEAR MATTE SEALER. OR IF PAINTING, A PRIMER/SEAL IS REQUIRED. FLAT PAINT IS RECOMMENDED, AND SPRAY APPLICATION PROVIDES THE BEST RESULTS.

## ADDITIONAL NOTES

- 20-30 MINUTES PER PANEL SHOULD BE ALLOTTED TO MOUNT AND SEAM PANELS PRIOR TO PAINT. (DRYING TIME OF CAULKING NOT INCLUDED). EXPERIENCE MAY SHORTEN INSTALLATION TIME.
- A DETAILED INSTALLATION BOOKLET ACCOMPANIES EACH ORDER.

12/06/23

## modulararts®

modularArts, Inc. I 206.788.4210 8207 South 192nd Street I Kent, WA 98032 modulararts.com I info@modulararts.com